

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

OCT 23 1978

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 009-00680-00-00 of this well)
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Palomine Petroleum

Complete Address 500 Insurance Bldg., Wichita, Kansas 67202

Lease Name Christians Well No. 3

Location E/2 NE SE Sec. 20 Twp. 16 Rge. 12 NE (W) X

County Barber Total Depth 3363'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 128 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 2:30 PM Day 19 Month 10 Year 1978

The above well was plugged as follows:

Sanded back to 2900' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 3 sx hulls, 25 sx mud gel, 1 sx hulls, and 100 sx cement.

Max. pres. 300#. Shut in pres. 500#.

Recovered 2570' of 5 1/2" casing.

Plugged back to 3030'. Top perforation at 2947'.

3361' of 5 1/2" casing cemented with 100 sx cement.

350' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane L. Rankin
Well Plugging Supervisor

DATE 10-24-78

INV. NO. 8359-W