

~~15-047-20463-00-00~~
15-047-20463-00-00

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

R

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - - (of this well)

Operator's Full Name Sterling Drlg., Co., et al

Complete Address Box 129-Sterling, Ks. 67579

Lease Name Mecum Well No. 1-18

Location C SE SE Sec. 18 Twp. 23 Rge. 19 (E) (W) X

County Edwards Total Depth 2610

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling.

Address Box 176-Chase, Ks. 67524 License No. 683

Operation Completed: Hour 12:30 Pm. Day 20 Month 10 Year 1979

The above well was plugged as follows:

249' 7" casing w/255 sax cement. 4 1/2" casing set at 2604' w/100 sax
cement. Plug back to 2450'-Preforated at 2413'-16" Sand back to 2350'-
Top sand w/4 sax mixed cement w/ dump bailer. Pull 2150' 4 1/2" casing.
Allied mixed & pumped 8 sax hulls-25 sax gel-75 sax 50/50 posmix cement
w/4% gel & 3% cc to top of casing. Shut in w/800# pressure. VED

STATE CORPORATION COMMISSION

OCT 25 1979

CONSERVATION DIVISION
WICHITA, KANSAS

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 10-24-79
INV. NO. 0708-W