

<sup>to</sup> KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

NOV 30 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name William Cohen

Complete Address: Box 2421, Wichita, Kansas

Lease Name E. Keenan "C" Well No. # 1

Location SW SW NE Sec. 26 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3842

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glen & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas License No. 396

Operation Completed: Hour 2:30PM Day 25th Month Nov. Year 1964

The Above well was plugged as follows:

193' of 8 5/8" surface pipe, cement circulated. 3660' of 5 1/2" long string,  
cemented with 100 sacks. Top perforation 3544'. Plug was pushed to 3530',  
sand, and cemented with 5 sacks. Fluid level was up in the hole. Bridge  
plug was set at 200', and 5' of rock bridge. 4 sacks of cement and 5%  
Calcium Chloride was mixed in a barrel, and put on plug at 195', through  
the dump Bailer, and let set for 3 hours. Then hole was bailed dry, and  
21 sacks of cement was added to the plug. Hole was filled with mud to 40',  
and 10' of rock bridge, and cemented with 10 sacks to the base of the cellar.

3033' of 5 1/2" long string was recovered from the hole.  
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 12/1/64

INV. NO. 240-W