

WELL PLUGGING RECORD

Give All Information Completely
Map Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rice County, Sec. 13 Twp. 21S Rge. 7W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE

Lease Owner The Cherry Drilling Co., Inc.

Lease Name DeWees Well No. 1

Office Address 102 Insurance Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 20, 19 57

Application for plugging filed October 20, 19 57

Application for plugging approved October 20, 19 57


Plugging commenced October 20, 19 57

Plugging completed October 20, 19 57

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 3480 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Layed down drill pipe, gunned pits to raise weight mud, circulated and brought heavy mud around. Built solid rock bridge to hold weight of drill pipe at 240' to 225'. Ran 15 sx. cement through 6 Jts. drill pipe. Top Bridge @ 35' with 5 sx. cement.

STATE CO. 10-24-57
OCT 21 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor The Cherry Drilling Co., Inc.

Address 102 Insurance Building, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss. Betty Brandt (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Betty Brandt

102 Insurance Building, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of October, 19 57

Lorraine Colaw Notary Public.

My commission expires July 25, 1960

PLUGGING
FILE SEC 13 T 21 R 7W
BOOK PAGE 56 LINE 11

15.159.00334.0000

CHERRY DRILLING CO., INC.
102 INSURANCE BUILDING
WICHITA 2, KANSAS

ROTARY DRILLING LOG

Lease DeWees	Company:	The Cherry Drilling Co., Inc. 102 Insurance Building Wichita 2, Kansas
Well No. 1		
Location NW SW SE Section 13-21S-7W Rice County, Kansas	Contractor:	The Cherry Drilling Co., Inc.
Elevation: 1597 D.F. 1595 Gr.	Geologist:	Robert W. Frensley 102 G Insurance Building Wichita 2, Kansas
Well Commenced: 10-10-57	Surface Pipe:	12 Jts. used 8 5/8" - 240' overall less thds., cemented with 175 sx. common cement, 2% CC
Well Completed: 10-20-57		

CASING: D & A

0 -240	Sand & red beds	2610-2670	Lime
240- 670	Shale & red beds	2670-2740	Lime & sand
670-1175	Shale, shells, anhydrite	2740-2895	Sand Lime
1175-1225	Shale & Shells	2895-2975	Lime
1225-1400	Lime & shale	2975-3075	Lime & sand
1400-1550	Fort Riley	3075-3130	Lime Shale
1550-1740	Shale Lime	3130-3375	Lime
1740-2180	Shale & lime	3375-3420	Lime & Chert
2180-2325	Lime Shale	3420-3446	Lime & Chaty
2325-2515	Lime & Shale	3446-3480	Lime Chert
2515-2610	Lime Shale	3480	R.T.D.

GEOLOGIST'S TOPS

Heebner	2686	(-1086)	Cherty Conglomerate	3427	(-1827)
Toronto	2700	(-1100)	Mississippi Chat	3462	(-1862)
Douglas Sand	2730	(-1130)	T. D.	3480	(-1880)
Lansing	2886	(-1286)			

The above is a true and correct log to the best of my knowledge.

PLUGGING	
FILE SEC	13 T 21 R7W
BOOK PAGE	56 LINE 11

STATE CORP.
OCT 24 1957
CONSERVATION DIVISION
WICHITA, KANSAS

Petty P. Pruitt
Assistant Secretary

Subscribed and sworn to before me on this 23rd day of October, 1957.

My Commission Expires July 25, 1960.

Lorraine Colaw
Lorraine Colaw Notary Public