

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-159-21,590.0000

LEASE NAME C.J. Johnson

WELL NUMBER 2-13

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4620 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 13 TWP. 21 RGE. 7W (E) or (W)

COUNTY Rice

Date Well Completed 06-09-83

Plugging Commenced 05-01-96

Plugging Completed 05-02-96

April 1996 (date)

LEASE OPERATOR Bruce Oil Company
1704 Limestone Road
ADDRESS McPherson, Kansas 67460

PHONE# 316, 241-2938 OPERATORS LICENSE NO. 5610

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____
by Jack Luthi (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Mississippian Depth to Top 3418 Bottom 3488 T.D. 3530

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Surface	soil, sand, sh	0	202	8 5/8	202	none
Mississippian	chert, lime	3418	3488	4 1/2	3488	2918

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Sanded off bottom to 3334 ft. Cap with 4 sacks portland cement with bailer.
Ripped pipe at 2900 ft. Pull pipe to 950 ft. and spot 35 sacks cement.
Pull pipe to 320 ft. and circulate cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sunflower Well Service

Address P.O. Box 341, Canton, Kansas 67428

KANSAS CORPORATION COMMISSION
30280
JUN 13 1996

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lonny Bruce

STATE OF Kansas COUNTY OF McPherson


Lonny Bruce

(Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Lonny Bruce

(Address) McPherson, Kansas

SUBSCRIBED AND SWORN TO before me this 11 day of June, 19 96



David W. Chartier
Notary Public