


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bifling Building
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 26 Twp. 21 Rge. 14 (K) (W)
Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner Petroleum, Inc.
Lease Name McGINTY 'B' Well No. 1
Office Address _____
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 11, 1954 1954
Application for plugging filed May 11, 1954
Application for plugging approved May 11, 1954
Plugging commenced May 11, 1954
Plugging completed May 11, 1954

Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. M. A. Rives
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3835' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	235'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded up to 220' and placed 1-1/2
gallon of Hulls in a sack ahead of
plug, set at 220'. Cemented and
displaced 20 sacks cement through
drill pipe onto plug and hulls at
220'. Mudded up to 35' and placed
1-1/2 gallon Hulls in a sack ahead
of plug set at 35'. Filled hole to
bottom of well cellar with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Company
Address R.R. #2, Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. W. Fisher (employee of owner) ~~or holder or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. W. Fisher
305 East Third, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of May, 19 54

My commission expires October 13, 1954.

Sharonne Meidman
Notary Public.

24-7988-S 3-53-20M

PLUGGING
FILE SEC 26T 21R 14W
BOOK PAGE 23 LINE 42

RECEIVED
STATE CORPORATION COMMISSION
MAY 2 1954
CONCE...
1954

WELL LOG

15.185.00974.0000

COMPANY Petroleum, Inc.

SEC. 26 T. 21S R. 11W

FARM MCGINTY 'B'

NO. 1

LOC. NW SW SW


TOTAL DEPTH 3835'

COUNTY Stafford County, Kansas

COMM. May 2, 1954

COMP. May 11, 1954.

CONTRACTOR Garvey Drilling Company



CASING 8-5/8" @ 233' w/175 sax.

ELEVATION 1935' R.B.

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

220	Sand
233	Blue Shale
375	Shale, Shells and Sand
825	Red Bed & Shells
860	Anhydrite
1770	Shale & Shells
1875	Lime & Shale
1990	Lime
3140	Lime & Shale
3745	Lime
3796	Lime & Shale
3835	Lime
3835	R.T.D.

Tops:

Heebner:	3290 (-1355)
Brown Lime:	3409 (-1474)
Lansing:	3420 (-1485)
Viola:	3690 (-1755)
Simpson:	3735 (-1800)
Arbuckle:	3790 (-1855)

RECEIVED
STATE OF KANSAS
COMMISSIONER
CONCERNING DIVISION
Wichita, Kansas

State of KANSAS
County of SEDGWICK } ss:

PLUGGING
FILE SEC 26 21R 11W
BOOK PAGE 33 LINE 12

I, W. W. Fisher of Petroleum, Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the MCGINTY 'B' #1 well.

W. W. Fisher

Subscribed and sworn to before me this 28th day of May, 19 54

My Commission Expires: October 13, 1954.

Charles H. Hurd
NOTARY PUBLIC