


15.185.20535.0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Stafford County, Sec. 26 Twp. 21 Rge. 14 E/W
Location as "NE/CNW $\frac{1}{2}$ /SW $\frac{1}{2}$ " or footage from lines SE-SW-NE
990ft from West Line 330ft from South Line
Lease Owner L. D. Davis
Lease Name Boxwell Well No. 1
Office Address Box 324 Great Bend, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Oil
Date Well completed September 19, 1974
Application for plugging filed July 8, 1976
Application for plugging approved July 16, 1976
Plugging commenced July 19, 1976
Plugging completed July 20, 1976
Reason for abandonment of well or producing formation _____

Not commercial any longer
If a producing well is abandoned, date of last production
July 1, 1976

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Corporation Comm.

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstine
Producing formation Kansas City Depth to top 3544 Bottom 3565 Total Depth of Well 3810
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Lansing K. C.</u>	<u>Oil</u>					
<u>Arbuckle</u>	<u>Dry</u>	<u>0</u>	<u>3809</u>	<u>4 1/2</u>		<u>1854ft</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dumped 25 gallons of sand at 3549 dumped 4 sacks of cement on top of sand.
Set 20ft rock bridge at 200ft. filled hole with 3 yards of ready mix to surface.

SEP 22 1976

9-22-76

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kincaid well Service #747

STATE OF Kansas COUNTY OF Barton, ss. and
L. D. Davis (~~employee or owner~~) or (owner ~~or~~ operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

L. D. Davis


Box 324 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of September, 1976

Elsie J. Learned

Elsie J. Learned Notary Public.

My commission expires 12-11-79



DRILLERS LOGBOXWELL NO. 1

CASING RECORD:
8 5/8" set at 242'
w/250 sacks cement

OPERATOR: WOLLAND, INC.

DESCRIPTION:

TOTAL DEPTH:

3810'

CONTRACTOR: SEARCH DRILLING COMPANY

COMMENCED: September 13, 1974

COMPLETED: September 19, 1974

SE SW NE,
Sec. 26-21S-14W
Stafford County,
Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand	0	100	
Sand and Shale	100	251	
Shale, Shells and Sand	251	830	
Anhydrite	830	854	
Shale	854	1116	
Shale, clay and salt	1116	1700	
Lime and Shale	1700	1775	
Lime	1775	1860	
Lime and Shale	1860	1955	
Lime and Shale	1955	2265	
Lime and Shale	2265	2600	
Lime and Shale	2600	2890	
Lime and Shale	2890	3150	
Lime and Shale	3150	3325	
Shale and Lime	3325	3409	
Lime	3409	3468	
Lime	3468	3550	
Lime	3550	3590	
Lime	3590	3620	
Lime	3620	3640	
Lime	3640	3760	
Cherty Lime and Lime	2760	3810	4 1/2" set at 3809' Cemented with 135 sacks 60-40 posmix, salt saturated.

RECEIVED
STATE CORPORATION COMMISSION

JUL 16 1976

CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

E. F. Day
E. F. DAY

Subscribed and sworn to before me this 20th. day of September, 1974

My commission expires:
February 19, 1977

Maxine Dressen
Maxine Dressen Notary Public

