

STATE OF KANSAS
STATE CORPORATION COMMISSION
DEC 11 1964


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

Mail or Deliver Report to:

Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Stafford County. Sec. 26 Twp. 21 Rge. 14 (E) W (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner William Cohen - Wichita Iron & Metals Corp
Lease Name E Keenan "C" Well No. 1
Office Address Box 2421 - Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 12/7/50 19__
Application for plugging filed Nov 18 1964
Application for plugging approved Nov 18 1964
Plugging commenced Nov 21 1964
Plugging completed Nov 25 1964
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production _____ 19__
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3842 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	193	none
	Log Attached			5 1/2	3660	3046'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set plug at 3530' - sand to 3520' and ran 5 sacks of cement from 3520' to 3490'.

Set plug at 200' rock bridge from 200' to 190' and ran 5 sacks of cement. Bailed out water and ran 15 sacks of cement from 190' to 130' - mudded from from 130' to 30' and ran 10 sacks of cement from 30' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn & Smith Pipe Pulling Co.
Address Box 156 - Ellinwood, Kansas

STATE OF _____, COUNTY OF _____, ss.

_____, (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Michael Iron & Metals Corp.
by Roy Stehall
Box 2421 - Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 10 day of December, 1964

My commission expires August 20, 1967

Eugene P. Martin
Notary Public.

15.185.01870.0000

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PETROLEUM, INC.

SEC. 26 T. 21 R. 14W

FARM Keenan "C"

NO. 1

LOC. SW SW NE

TOTAL DEPTH 3842

COUNTY Stafford


COMM. 11-26-50

COMP. 12-7-50

SHOT OR TREATED

KANSAS

CONTRACTOR Garvey Oil



ISSUED 2-17-51

CASING

8 5/8" 193'

5 1/2" 3660'

ELEVATION 1935 D.F.

PRODUCTION I. P. P. 36 /
33% wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

surface & clay	50
sand & shale	150
shale & shells	193
sand & clay	275
sand	345
red bed	720
anhyd.	860
shale & shells	1420
lime & shale	1770
lime	1780
lime & shale	2080
shale & shells	2365
lime & shale	2911
lime	3149
shale	3344
lime & shale	3425
lime	3460
lime & shale	3685
Viola	3737
shale	3751
lime	3825
lime	3842
Total Depth	

Tops:	
Heebner	3288
Brown lime	3408
Lansing	3419
Viola	3695
Simpson	3742
Arbuckle	3795

D.S.T. # 1 3541-3552. Open 1 hr.
rec. 90' heavy oil cut mud.
D.S.T. # 2 3582-3610. Open 1 hr.
rec. 45' heavy free oil & 20' oil
cut mud.

RECEIVED
STATE CORPORATION COMMISSION

DEC 21 1964

CONSERVATION DIVISION
Wichita, Kansas