

15.185.20069.0000

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Stafford SEC. 6 TWP. 21 RGE. 14 ~~EW~~
 Location as in quarters or footage from lines:
 SW/NW/SW

Locate Well
 correctly on above
 Section Platt.

Lease Owner John O. Farmer, Inc.
 Lease Name Barrett Well No. #1
 Office Address Box 352 - Russell, Kansas 67665
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced May 13, 1982
 Plugging completed May 21, 1982
 Reason for abandonment of well or producing formation
Depleted

Was permission obtained from the Conservation Division or it's
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well J. H. Metz

Producing formation _____ Depth to top _____ bottom _____ T.D. 3700'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8"	887'	NONE
				5 1/2"	3699'	2803.42'

Describe in detail the manner in which the well was plugged, indicating where the mud
 fluid was placed and the method or methods used in introducing it into the hold. If cement
 or other plugs were used, state the character of same and depth placed, from _____ feet
 to _____ feet for each plug set.

Dumped sand to 3650' and five (5) sacks cement.
Shot pipe @ 3000', 2900' and 2800'.
Pulled ninety-two (92) joints of 5 1/2" casing.
Squeezed well with four (4) sacks hulls, twenty-five (25)
sacks cement, twenty-five (25) sacks gel, one (1) sack
hulls, one hundred fifteen (115) sacks 50/50 pozmix
cement with 4% added gel and 3% calcium chloride.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rockhold Engineering, Inc.

STATE OF KANSAS COUNTY OF BARTON, ss.


James W. Rockhold (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
 JAMES W. ROCKHOLD - Box 698 - Great Bend, Ks.
 (Address) 67530

SUBSCRIBED AND SWORN TO before me this 10th day of June, 19 82

Jo A. Dewell
 Jo A. Dewell Notary Public.

My Commission expires:



RECEIVED
 STATE CORPORATION COMMISSION
 JUN 26 1982 6-14-82
 CONSERVATION DIVISION
 Wichita, Kansas

WELL LOG

COMPANY	James Mooneyham, et al
CONTRACTOR	Vaughan Drilling, Inc.
FARM	#1 Barrett
LOCATION	SW NW SW of Sec. 6-21-14W Stafford County, Kansas
ELEVATION	1934 KB
SURFACE PIPE	8 5/8" cemented w/450 sx cement @ 837'
PRODUCTION	set 5 1/2" oil string w/150 sx @ 3703'
COMMENCED	11/9/67
COMPLETED	11/21/67

<u>Formation</u>	<u>Depth</u>
SURFACE CLAY	313'
shale sand	415
shale and sand	440
red red bed	874
Anhydrite	903
shale and shells	1880
lime w/shale	2000
lime	2095
lime and shale	2993
lime lime	3630
Arbuckle	3700
R.T.D.	3704

RECEIVED
STATE CORPORATION COMMISSION
APR - 9 1967
CONSERVATION DIVISION
Wichita, Kansas

A F F I D A V I T

STATE OF KANSAS
COUNTY OF SEDGWICK

I, Donald D. Vaughan, of the VAUGHAN DRILLING, INC., being first duly sworn on oath, state that I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

Donald D. Vaughan
Donald D. Vaughan, President

Subscribed and sworn to before me this 22nd day of November, 1967.

My commission expires: 3/10/71

Carolyn Sinning
Carolyn Sinning NOTARY

Phone 316-483-2627, Russell, Kansas
 Phone 316-793-5861, Great Bend, Kansas

15.185.20069.0000

Phone Plainville 913-434-2812
 Phone Kiowa 316-825-4618

ALLIED CEMENTING CO., INC.

Home Office P. O. Box 31

Russell, Kansas 67665

No 27753

Date	5-21-82	Sec.	6	Twp.	21	Range	14W	Called Out	6:30	On Location	8:45	Job Start	9:15	Finish	10:15	
Lease	BARRATT	Well No.	#1	Location				Radium ST-56 ST-56 1/2	County	STAFFORD	State	KAN				

Contractor	Rock Hold Inc	Owner	John E. W.
Type Job	Old Hold	To Allied Cementing Co., Inc. You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as listed.	
Hole Size		T.D.	
Csg. Size		Depth	
Tbg. Size		Depth	
Drill Pipe		Depth	
Tool		Depth	
Cement Left in Csg.		Shoe Joint	
Press Max.		Minimum	
Meas Line		Displace	
Perf.			

Charge To	J.O. FARMER
Street	Box 352
City	Russell
State	KAN 67665
The above was done to satisfaction and supervision of owner agent or contractor.	

EQUIPMENT		
No	Cementer	PARSON
Pumptrk 63	Helper	DOUG
No	Cementer	
Pumptrk	Helper	
	Driver	OTIS
Bulktrk 116		
Bulktrk	Driver	

Purchase Order No.	
X	
CEMENT	
Amount Ordered	140 5% 4 1/2 gal 2 1/2 gal
Consisting of	5 hulls 25 gal
Common	70 475
Poz. Mix	70 185
Gel.	31 675
Chloride	3 20.00
Quickset	

DEPTH of Job	
Reference:	
	Pump Truck 340.00
	Plug 10.00
	14 Mileage 100
	Sub Total
	Tax
	Total

Handling	90
Mileage	14 .60
	Sub Total
	Total

Remarks: Mixed 4 hulls 25 cement
 Released Plug 115 cement
 Closed in at 600

25 gal 15 hulls
 Pumping Parson
 State Plug on loc.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 26 1982
 CONSERVATION DIVISION
 Wichita, Kansas