

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15.185.21065.0000

LEASE NAME Fry

WELL NUMBER B-4

 Ft. from S Section Line

 Ft. from E Section Line
 NE SW SE

SEC. 6 TWP. 21 RGE. 14W(E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 4-27-88

Plugging Completed 5-6-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS Box 6
 Great Bend, Kansas 67530

PHONE#(316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3712'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	883'	none
				5-1/2"	3698'	2278'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 3640' and 5 sacks cement. Shot pipe @3189', 2700', 2500', 2278', pulled a total of 58 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.
 (If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct so help me God.

(Signature) R. Darrell Kelso


(Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 9th day of May, 19 88

Jane Hoover
 Notary Public

My Commission Expires:

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 11 1988
 CONSERVATION DIVISION
 Wichita, Kansas



cc: WFD
6-5-80

15.185.21065.0000

DRILLERS WELL LOG

L. D. DRILLING, INC. - CONTRACTOR

N. C. R. A. - OPERATOR

FREY "B" 4
NE-SW-SE
Sec. 6-21S-14W
STAFFORD COUNTY, KANSAS

ELEV. 1927
T. D. 3702

COMMENCED: 5-27-80
COMPLETED: 6-2-80

CASING:
8-5/8" set at 883'
5-1/2" set at 3698 (4' off bottom)

CEMENT:
W/100 sx. Common, 3% CC
W/300 sx. Common Cement 2% Gel, 3% CC
W/100 sx. 50/50 Pozmix, 18% Salt Sat.

<u>FORMATION</u>	<u>DEPTH</u>
Sand	0 - 190
Blue Shale	190 - 310
Sand	310 - 404
Red Bed	404 - 874
Anhy.	874 - 895
Shale	895 - 2005
Shale W/Lime	2005 - 2305
Lime & Shale	2305 - 3040
Lime	3040 - 3702
R.T.D.	3702

<u>TOPS</u>	
Heebner	3257
B. Lime	3358
Lansing	3367
Viola	3614
Simpson Shale	3647
Arb.	3694
R.T.D.	3702

STATE OF KANSAS }
COUNTY OF BARTON } ss

I certify that this is a true and correct copy of the above log to the best of my knowledge.

L. D. DRILLING, INC.

L. D. Davis
L. D. Davis

RECEIVED
STATE CORPORATION COMMISSION

Sworn to and subscribed before me this 3rd day of May, 1980.

My appointment expires: 3-28-80

Bessie M. DeWerrif
Bessie M. DeWerrif, Notary Public

APR 27 1988

CONSERVATION DIVISION
Topeka, Kansas

BESSIE M. DEWERIFF
STATE NOTARY PUBLIC
BARTON COUNTY, KANSAS
MY APPT. EXP. 3-28-81