

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15.185.10777.0000

LEASE NAME Fry

WELL NUMBER B-2

 Ft. from S Section Line

 Ft. from E Section Line
 SW NE SE

SEC. 6 TWP. 21 RGE. 14W(E) or (W)

COUNTY Stafford

Date Well Completed

Plugging Commenced 5-3-88

Plugging Completed 5-6-88

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR N.C.R.A.

ADDRESS Box 6
Great Bend, Kansas 67530

PHONE (316) 793-7824 OPERATORS LICENSE NO. 5565

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? Yes

Which KCC Office did you notify? Dist. #1 Dodge City, Kansas

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.D. 3702'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	880'	none
				5-1/2"	3684'	2927'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged off bottom with sand to 3630' and 5 sacks cement. Shot pipe @2927', pulled a total of 99 joints of 5-1/2" casing. Plugged surface with 4 hulls, 10 gel, 50 cement, 10 gel, 1 hull, plug and 100 cement, 60/40 pos, 6% gel. Plugging Complete.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347 Chase, Kansas 67524

SWORN TO before me this 9th day of May, 19 88

Jane Hoover
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 SUBSCRIBED AND SWORN TO

Commission Expires:

CONSERVATION DIVISION
 Wichita, Kansas

5-11-88




Company Vickers
 Lease Frey #B Well No. 2
 Location SW 1/4 SE Sect. 6 Twp. 21S Rge. 14 W.

Date commenced March 22, 1951
 Date completed April 16, 1951

Contractor Jayhawk Drilling Co., Inc.

Elevation 1926 P.B.
 Producing formation Arbuckle
 Top producing formation 3683' (-1757)
 Total depth 3702 Zero: 7' 10" above 8-5/8" head
 Size hole made (1776)



Casing record:	Make	Threads	Weight	Size	Feet	Cemented
Surface	J-55	8Rd	24#	8 5/8	880	400 ex
Oil string	J-55	8Rd	15#	5 1/2	3684	75 ex
					(-1758)	

Tubing record:
 Make J-55 Sals Kind EUE 8Rd thd
 Size 2" Weight 4.70#
 Ave. joint length 30.6 (119 Jts)
30' 9" P&A 6" pup joint
 Working barrel:
 Make Common
 Size 1 3/4 x 10

Deepening or plug back record:

~~2334
 2335
 1926
 1428~~

Tubing perforations set at 3670'

Rods: 145
 Make D & B
 Type Heat-Treat Size 3/4 x 25'
4' pony rod
 Valves: D & B Pump (Wood Type)
 Make Common Size 2 x 1 1/2 x 9
2' pony rod on pump

Pumping Unit:
 Make Emeco Size 109 M.D.
 Serial No. 379
 Gear ratio 36.6 to 1

Power:
 Make Witte Size Model "C"
 Serial No. 3982

Acid 2,000 Gal. Casing Method
 Acid by Dowell, Inc.

Potential Phy. 99 BOPD No % Water
 Kind of potential Physical
 Potential data:

Rate	SPM	Length Stroke	BFPH	Fluid Level	BFPD
High					
Inter					
Low					

REMARKS

Top:	
Heebner	3245'
Brown Line	3345'
Lansing	3354' - 1428
Viola	3604'
Simpson	3640'
Arbuckle	3683'

DST: 3607-3632, open 15 min. weak blow, died in 6 min. recovered 4' mud.

Cable Tools: Drld plug and clean out to 3690' Drld deeper to 3652. Fill up to 325' oil in 14 hrs. Drld deeper to 3702 T.D. Fill up 1100' oil in 18 hrs. Acidized w/1000 gal. Filled up 350' oil in 14 hrs. 48 cone shots 3686-3700' Fill up 425' oil in 14 hrs. Acidized w/2000 gal. Filled up 1500' oil in 14 hrs. Swabbed 5 B OPH for 5 hrs.

22" Sheave on Unit.
 12" Sheave on Engine
 10-1000 V Belts
 8-5/8" x 5 1/2" Hinderliter csg head
 5 1/2" x 2" Hinderliter Tubing Head
 890' 8" (35 Jts) New 3" L/P lead line