

LEASE NAME Chapman

WELL NUMBER #1

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 32 TWP. 21 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 8-27-48

Plugging Commenced 2/24/93

Plugging Completed 3/5/93

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Hallwood Petroleum, Inc.

ADDRESS 4582 So. Ulster St. Pkwy., #1700, Denver, CO 80237

PHONE# (303) 850-7373 OPERATORS LICENSE NO. 3613

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/5/93 (date)

by Duane Rankin (KCC District Agent's Name).

Is ACC-1 filed? Yes if not, Is well log attached?

Producing Formation NA Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Anhydrite	water		770'	8 5/8	295'	-0-
				5 1/2	3638'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each section. Perf salt section @ 2000 ft. w/4 holes, perf Anhydrite @ 770 ft. w/4 holes.

Spot 15 sx gel & 10 sx gel w/hulls, spot 40 sx 60/40 poz @ 2977'. Pull 32 jts and pumped cement to spot @ 2030. Pull 39 jts and pump 320 sx 60/40 poz. Pump 20 sx down 5 1/2 casing. Pump 80 sx 60/40 poz w/6% gel.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Halliburton License No. 5287

Address 2400 Main St., Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Hallwood Petroleum, Inc. STATE CORPORATION COMMISSION

STATE OF Colorado COUNTY OF Denver, ss.

Jim L Linville Jr Petroleum Engineer (Employee of Operator Conservation Division)

above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P.O. Box 378111 Denver CO 80237

SUBSCRIBED AND SWORN TO before me this 22 day of March, 19 93

Audrey h. Marcian
 Notary Public

Commission Expires: Sept. 8, 1996

