

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Stafford County, Sec. 11 Twp. 21 Rge. 14W (xx) (W)

Location as "NE/CNW/SW" or footage from lines C N/2 SE

Lease Owner C. H. Spoor Jr.

Lease Name Hullett Well No. 1

Office Address 1078 N. Armour Lane Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 19

Plugging completed November 15, 19 63

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well A. Elving

Producing formation Depth to top Bottom Total Depth of Well 3700' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

278' of 8 5/8" surface pipe, cemented with 250 sacks. Fluid level was up in hole. 1st cementing plug and 1/4 sack hulls, was pushed to 275' cemented with 25 sacks, through drill pipe. Hole was filled with drilling mud to 40', 2nd cementing plug, bridged with 1/2 sack hulls, cemented with 10 sacks to base of cellar. Rat Hole bridged and cemented with 2 sacks.

RECEIVED
STATE CORPORATION COMMISSION

APR 18 1966

Name of Plugging Contractor Prime Drilling Company
Address 814 Union Center Wichita, Kansas

STATE OF _____, COUNTY OF _____, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. H. Spoor, Jr.

SUBSCRIBED AND SWORN TO before me this 14th day of April, 1966
Edward S. Frenchie

My commission expires 11-5-67 Notary Public.

ROTARY DRILLING LOG

OWNER: C. H. Spoor, Jr.
 CONTRACTOR: Prime Drilling Company
 LEASE: Hillatt #1
 LOCATION: SE NW SE Sec. 11-215-14W
 Stafford County, Kansas

CASING: Set 5 5/8" surface casing
 @ 278', 250. ex. Pm. MA-5

0 - 200	Sand
200 - 278	Sand & Shale
278 - 615	Sand & Red Bed
615 - 1685	Shale & Shells
1685 - 1928	Shale & Lime
1928 - 2165	Lime
2165 - 2380	Lime & Shale
2380 - 2645	Shale & Lime Streaks
2645 - 2918	Shale & Lime
2918 - 3253	Lime & Shale
3253 - 3645	Lime
3645 - 3700	Lime & Chert
	Rotary Total Depth

D & A


RECEIVED
 STATE CORPORATION COMMISSION

FEB 18 1964

CONSERVATION DIVISION
 Wichita, Kansas

We certify that the above log is true and correct to the best of our knowledge and belief.

PRIME DRILLING COMPANY

BY 
 L. J. Clappitt