


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

STAFFORD County. Sec. 11 Twp. 21S Rge. 14 ~~XXX~~ X (W)
Location as "NE/CNW/SW" or footage from lines NE NW NW
Lease Owner WESTERN PETROLEUM CO., INC.
Lease Name BOESE Well No. 2
Office Address 925 PATTON ROAD, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) OIL WELL
Date well completed JUNE 3 19 57
Application for plugging filed APRIL 20 19 60
Application for plugging approved APRIL 25 19 60
Plugging commenced APRIL 21 19 60
Plugging completed APRIL 25 19 60
Reason for abandonment of well or producing formation NO LONGER
COMMERCIALY PRODUCTIVE.
If a producing well is abandoned, date of last production NOVEMBER 19 59
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES.

Name of Conservation Agent who supervised plugging of this well FRANK BROADFOOT
Producing formation LANSING-KANSAS CITY Depth to top 3462' Bottom 3553 Total Depth of Well 3690 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
SAND	WATER		181'	8-5/8"	5/23/57	
LIME	OIL	3460'	3472'	5-1/2"	6/3/57	4/25/60

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

PLACED 50 FEET OF CRUSHED ROCK FROM 3485' TO 3435'.

RAN 5 SACKS OF CEMENT. PUMPED IN 38 BARRELS OF MUD,

70 SACKS OF CEMENT. CEMENT DRIFTED 30 FEET. RAN

10 SACKS CEMENT TO THE BASE OF THE CELLAR.

RECEIVED
STATE CORPORATION COMMISSION

RECEIVED
STATE CORPORATION COMMISSION

MAY 11 1960

5-11-60

MAY 9 1960

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor CLAY CASING PULLING
Address FILLINWOOD, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
JOHN H. VOLOSIN (employee of owner) ~~owner~~ ~~operator~~

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

John H. Volosin

JOHN H. VOLOSIN, PRODUCTION SUPT.
WESTERN PETROLEUM CO., INC. - 925 PATTON ROAD
GREAT BEND, KANSAS (Address)

SUBSCRIBED AND SWORN to before me this 6TH day of MAY, 19 60

Reva C. Brown
REVA C. BROWN

Notary Public.

My commission expires JANUARY 15, 1963

WESTERN Petr. Corp.

DRILLER'S LOG

COMPANY: HILTON DRILLING COMPANY, INC.

LOCATION: NE NW NW

CONTRACTOR: HILTON DRILLING COMPANY, INC.

SECTION 11-213-14W
STAFFORD COUNTY, KANSAS

FARM NAME: BOESE No. 2

ELEVATION: 1915 D. F.
1918 K. B.

COMMENCED: MAY 22, 1957

COMPLETED: JUNE 3, 1957

CASING USED: 8-5/8" SET @ 362' w/250 SKS.
5-1/2" SET @ 3688' w/125 SKS.

CLAY AND SAND	205
SHALE	255
SAND AND SHALE	340
SHALE AND RED BED	363
RED BED, SHALE AND SHELLS	820
ANHYDRITE	845
SHALE AND SHELLS	870
SHALE AND LIME	1640
BROKEN LIME	1750
LIME	1875
LIME AND SHALE	2245
LIME	2905
LIME AND SHALE	3329
LIME	3370
LIME, SHALE, AND CHERT	3610
LIME	3647
LIME, SHALE, AND CHERT	3690
TOTAL DEPTH	3690

VED
COMMISSION
MAY 9 1960
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF BARTON } SS.

I, THE UNDERSIGNED, BEING DULY SWORN ON OATH, STATE THAT THE ABOVE STATEMENT AND LOG ARE TRUE AND A CORRECT RECORD AND LOG OF THE WELL DRILLED AT THE LOCATION ABOVE-DESCRIBED.

HILTON DRILLING COMPANY, INC.

SUBSCRIBED AND SWORN TO, BEFORE ME THIS 7TH DAY OF MAY, 1957.

NOTARY PUBLIC

MILDRED HOBBS
MY COMMISSION EXPIRES MARCH 5, 1958

