

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 2 1964
 1-2-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Bill Blackburn of Terrel Drilling Co. has this date requested permission to plug the following described well:

Mr. Blackburn guarantees payment of the plugging fee.

Operator's full Name: James W. Hershberger

Complete Address: 1039 1st National Bank Bldg., Wichita, Ks.

Lease Name: Schmitt Well No. # 1

Location: C NW NW Sec. 29 Twp. 23 Rge. 20 (E) (W) W

County Edwards Total Depth 4750 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Blackburn was instructed to plug the well as follows:

284' of 8 5/8" surface pipe, cemented with 175 sacks.
Fill hole with mud to 280', 1st cementing plug, bridge
with hulls, cement with 25 sacks. Fill hole with mud to
40', 2nd cementing plug, bridge with hulls, cement with
10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent