

State of Kansas



RECEIVED  
STATE CORPORATION COMMISSION

15-159-20063-0000

SEP 22 1967

State Corporation Commission

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

CONSERVATION DIVISION  
Wichita, Kansas

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

9-25-67

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

September 12, 1967

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Clarence Herman of Wofford Oil Company has this

date requested permission to plug the following described well:

Mr. Herman guarantees payment of the plugging fee.

Operator's full Name: Wofford Oil Company

Complete Address: 1258 Cleveland, Wichita, Kansas

Lease Name: Berniece Warnock Well No. 1

Location: C SW SE Sec. 22 Twp. 21 Rge. 7 RD (W) X

County Rice Total Depth 3420' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Herman was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and

cement hole with 25 sacks through drill pipe. Fill hole with mud to

40'. Push plug and 1/2 sack hulls to 40' and cap hole with 15 sacks

cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

William J. Loomis  
Conservation Division Agent