



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 16 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Parks of Gabbert-Jones Drlg. has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Robert R. Price & Aspen Drlg. Co.

Complete Address: Tulsa, Okla.

Lease Name: Darnall Well No. 1

Location: SE SE Sec. 4 Twp. 21 Rge. 19 (E)(W) XX

County: Pawnee Total Depth 4386' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Parks was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 600' and displace

50 sc cement thru drill pipe. Heavy mud to 390' set cementing plug and

displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole

with 2 sc cement.

Very truly yours,

[Signature]
Conservation Division Agent