



15.113.30110.0000

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1966
8-12-66
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Anderson of George R. Hess has this

date requested permission to plug the following described well:

Mr. Anderson guarantees payment of the plugging fee.

Operator's full Name: George R. Hess

Complete Address: 505 North Charles. McPherson, Kansas

Lease Name: Rrank Unruh Well No. # 3

Location: SE SE NE Sec. 3 Twp. 20 Rge. 2 (E) (W)

County McPherson Total Depth 2990' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Anderson was instructed to plug the well as follows:

8 5/8"-125'-Circulated w/cement. 5 1/2"-2967'-Cemented. Sand hole to 2950'.

5 Sax.cement 2950' to 2900! Mud 2900' to 160'. Bridge 160' to 150'.

25 Sax.cement 150' to 75'. Mud 75' to 40'. Bridge 40' to 30'.

10 Sax.cement 30' to 0.

Very truly yours,


Conservation Division Agent