



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

JUN 1 1970

CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Curtis of Duke Drlg. Co. Inc. has this  
date requested permission to plug the following described well:

Mr. Curtis guarantees payment of the plugging fee.

Operator's full Name: F. G. Holl

Complete Address: 6427 E. Kellogg Wichita, Kansas

Lease Name: Espey Well No. 1

Location: SW/4 NE/4 NW/4 Sec. 25 Twp. 21 Rge. 11 (E) (W) W

County: Stafford Total Depth 3466 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Curtis was instructed to plug the well as follows:

250 ft. of 8 5/8 surface pipe cemented with 225 sacks.

Set bottom plug at 500 ft, 50 sacks cement. Plug at 240 ft,

25 sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10

sacks cement to surface. 2 sacks cement in rat hole.

Cemented by Sun Cementing Co.

Very truly yours,

*J. Russell Biberstein*  
Conservation Division Agent