

State of Kansas



15-185-01379-0000 FORM - CP-2

JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

1-6-64 JAN 6 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Copeland of Western Petroleum Co. has this  
date requested permission to plug the following described well:

Mr. Copeland guarantees payment of the plugging fee.

Operator's full Name: Don Moore Associates, Inc.

Complete Address: 918 Central Bldg., Wichita, Kansas

Lease Name: Isern-Bever Well No. # 1

Location: NE NE NE Sec. 24 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3490 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Copeland was instructed to plug the well as follows:

240' of 8 5/8" surface pipe, cemented with 260 sacks. Fill  
hole with mud to 250', 1st cementing plug, bridge with hulls,  
cement with 25 sacks. Fill hole with mud to 40', 2nd cement-  
ing plug, bridge with hulls, cement with 10 sacks to base  
cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent