



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

August 3, 1970

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 10 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock,
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ralph Watson of Knight Casing Pulling Co., Irmas this
date requested permission to plug the following described well:

Mr. Watson guarantees payment of the plugging fee.

Operator's full Name: Pheonix Drilling Company

Complete Address: Suite 20-400 N. Woodlawn, Wichita, Kansas 67208

Lease Name: Werner Unit Well No. 1

Location: C SW SW Sec. 3 Twp. 21 Rge. 9 (E) (W) X

County: Rice Total Depth 3030' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Watson was instructed to plug the well as follows:

Push 4 1/2" plug to 2960'. Fill hole with sand to 2950' and cement with
3 sacks cement. Bail hole to 205'. Set rock bridge from 205' to 195'
and cement hole with 25 sacks cement. Fill hole with mud to 40'. Set
rock bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,


Conservation Division Agent