

State of Kansas



15.159.20053-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 23, 1967

RECEIVED
STATE CORPORATION COMMISSION

AUG 1 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Frank Pfannenstiel of Leben Drilling, Inc. has this date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: A. Scott Ritchie

Complete Address: 413 Union Center, Wichita, Kansas 67202

Lease Name: Jeter Well No. 1

Location: C SW SE Sec. 3 Twp. 21 Rge. 9 (E) (W) X


County Rice Total Depth 3000' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pfannnstiel was instructed to plug the well as follows:

Fill hole with mud to 215'. Push plug and 1/4 sack hulls to 215' and cement hole with 25 sacks through drill pipe. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,


Conservation Division Agent