

KANSAS

*Handwritten mark*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 3 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name J.D. Mooneyham

Complete Address Box 11b Beverly, KS

Lease Name Erickson Well No. 1

Location NW/NE/NW Sec. 27 Twp. 21 Rge. 11 (E) W

County Stafford Total Depth 3460

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Knight Casing Pulling Co. Inc.

Address Box 405 Chase, Ks License No. 436

Operation Completed: Hour 3:30 PM Day 1 Month 9 Year 1971

The above well was plugged as follows:

246 ft 8 5/8 surface pipe cemented with 250 sacks. 4360 ft 4 1/2 long  
string cemented with 250 sacks. Top perf. 3380 ft. Sand back to  
3370 ft, 4 sacks cement with bailer. Pulled 2816 ft 4 1/2. Pump 3 sacks  
hulls, 15 sacks gel, 100 sacks cement to surface.

Pumped by Allied Cementing Co. Russell, Ks

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: L. Russell Bickstein  
Well Plugging Supervisor

DATE 9-3-71

INV. NO. 4279-W