

R 5P

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

12-15-1964

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Frank J. Black

Complete Address: Box 150, McPherson, Kansas

Lease Name U. S. Government "B" Well No. # 1

Location SW NE SE SE SE Sec. 26 Twp. 21 Rge. 11 (E) (W) W

County Stafford Total Depth 3776

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 2:30PM Day 14th Month Dec. Year 1964

The Above well was plugged as follows:

460' of 8 5/8" surface pipe, cement circulated. 3469' of 5 1/2" long
string, cemented with 100 sacks. Plug back to 3200'. Top perforation
3180'. Bottom of the hole was sanded to 3150', and cemented with 4
sacks. Hole was filled with mud to 300', and 10' of rock bridge, and
cemented with 25 sacks. Hole was filled with mud to 40', and 10' of
rock bridge, and cemented with 10 sacks to the base of the cellar.
2800' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 12-15-64

INV. NO. 350-W