

15.185.30478-0001

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 7 1966

CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Rains & Williamson Oil Company

Complete Address: 1425 Wichita Plaza, Wichita, Kansas

Lease Name Colvin Well No. # 1

Location C NE SE SE Sec. 22 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3820'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Company

Address: Box 405, Chase, Kansas License No. 436

Operation Completed: Hour 10:00AM Day 6th Month July Year 1966

The Above well was plugged as follows:

262' of 8 5/8" surface pipe, cement circulated. 3807' of 4 1/2" long
string, cemented with 150 sacks. This is an open hole. Bottom of the
hole was sanded to 3800', and cemented with 3 sacks, through the dump
bailer. Pipe parted at 1450'. 1450' of 4 1/2" long string was recovered
from the hole. Bridge plug was pushed in fluid to 260', rock and sand
bridge from 260' to 230'. 5 sacks of cement with 5% calcium chloride
was mixed in a barrel, and put on plug at 230', through the dump bailer,
and let set over-night. Next day hole was bailed dry, and 20 sacks of cement
was added to the plug. Hole was filled with mud to 40', rock bridge from 40'
to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 7-7-66

INV. NO. 3524-W