

15.185.30180.0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Time Petroleum Company

Complete Address: 815 Union National Bldg., Wichita, Kansas

Lease Name Meier Well No. # 1

Location SW NW SW Sec. 22 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3740'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Strata Drilling Inc.

Address: 2421 Tenth St., Great Bend, Kansas License No. _____

Operation Completed: Hour 2:15AM Day 14th Month Nov. Year 1964

The Above well was plugged as follows:

272' of 8 5/8" surface pipe, cement circulated. Hole was full with fluid.
1st cementing plug and 1/4 sack of hulls was pushed in fluid to 260', and
cemented with 25 sacks, through the drill pipe. Fluid level was now at
38' in the hole. 2nd cementing plug, bridged solid with hulls and dry
cement on fluid at 38', and cemented with 10 sacks to the base of the
cellar. Rat and mouse hole bridged and cemented with 5 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 11/16/64

INV. NO. 175-W