

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 4 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued November 27, 1967.

Operator's Full Name D. R. Lauck Oil Company, Inc.

Complete Address: 301 South Broadway, Wichita, Kansas 67202

Lease Name Fullerton Well No. # 1

Location SE SE SE Sec. 20 Twp. 21 Rge. 14 (E) (W) W

County Stafford Total Depth 3820'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Glenn & Smith Casing Pulling Company

Address: Box 156, Ellinwood, Kansas 67526 License No. 396

Operation Completed: Hour 8:35AM Day 30th Month November Year 1967

The Above well was plugged as follows:

249' of 8 5/8" surface pipe, cement circulated. 3820' of 5 1/2" long string, cemented with 125 sacks. Plug back T.D. 3790'. Top perforation 3751'. Bottom of the hole was sanded to 3725', and cemented with 5 sacks, through the dump bailer, with cement from 3725' to 3685'. 3030' of 5 1/2" long string was recovered from the hole. Hole was flowing with water, and was squeezed. 10 sacks of Gel-Mud and 80 sacks of cement was pumped into the surface pipe, through a 5 1/2" nipple with the braden closed in, to a pressure of 100 lbs., with cement from 240' to the base of the cellar. This cementing was done by Sun Cementing Company.

I hereby certify that the above well was plugged as herein stated.

Signed: Archie Elving
Well Plugging Supervisor

INVOICED

DATE 12/5/67

INV. NO. 6833-4