

130

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. \_\_\_\_\_

LOCATION SW-7W-SW

SEC. 23 TWP. 21 RGE. 14-W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 1 Lease Vauvrickle

Operator Steeling Drilling Co Address Steeling-Kans-

Field \_\_\_\_\_ County Stafford

Total Depth 3779 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2" - 310 ft. Circulated with cement  
3/4" casing set at 3777 ft. Cemented with 100 sacks cement  
Tare Wells Plug at 3570 ft. Filled with chat from 3570 ft  
& 3550 ft - Drilled 5 sacks of cement at 3550 ft - Shot off  
& Pulled the 3/4" casing - Well Flowing Salt Water  
Pumped hole full of heavy mud - 70 bbls - then  
Pumped in Plug & 100 sacks of cement - Filling  
hole from 310 ft to the surface with cement -  
Mud & Cement Pumped in by Halliburton*

**PLUGGING**  
FILE SEC 23-71-R-140  
BOOK PAGE 31 LINE 16

OCT 25 1950  
CONSERVATION DIVISION  
Wichita, Kansas  
District Conservation Agent

Date 10-21-50

X