

1 090390

15-175-01404-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION E/2 SE NE
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 2-5-54
SE NE, SEC. 31, T23 S, R 15 (W/)

3300 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Benson Unit Well # 105

Operator: Cities Service Oil & Gas Corp.
Name & Address: 3545 NW 58th Street.
Oklahoma City, OK 73112

County Pawnee 126.78

Well Total Depth 3901 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 pm Day: 9 Month: January Year: 19 86

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3899' PBTB 3825' Perfs at 3610-3854' CIBP at 3825'

1st plug sand back to 3560' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 12:50 pm Day: 9 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3560' and dumped 5 sx cement on top

of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JAN 16 1986

Maximum pressure 400 psi and shut in 150 psi CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2300' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

(If possible) observe this plugging.

INVOICED

DATE 1-16-86

Signed Robert A. Barlett
(TECHNICIAN)

INV. NO. 12088