

1 090391

15-145-01385-00-02

No Docket No. available

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW SE NE  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Completed 2-10-53  
\_\_\_\_\_ , SEC. 31 , T 23 S, R 15 W/X

3630 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5447

Lease Name Benson Unit Well # 102W (SWD)

Operator: Cities Service Oil & Gas Corp.  
Name & Address 3545 NW 58th Street  
Oklahoma City, OK 73112

County Pawnee 135.85

Well Total Depth 4180 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 467

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well X D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 pm Day: 9 Month: January Year: 19 86

Plugging proposal received from Roger Lusk

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4179' PBTD 3942' Perfs at 3620-3864'; 3771-4110'

1st plug sand back to 3570' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 pm Day: 9 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3570' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JAN 16 1986

Maximum pressure 300 psi and shut in 0 but no vacuum

CONSERVATION DIVISION Wichita, Kansas

Remarks: Recovered 2300' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

INVOICED

DATE 1-16-86

Signed Robert Starbuckton (TECHNICIAN)

INV. NO. 12080