

1 080479

15-145-01458-0002

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 12-29-46

NE SE NW, SEC. 32, T23 S, R 15 ~~WXX~~

3630 feet from S section line

2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Benson Unit Well # 201

Operator: Cities Service Oil & Gas Corp.

County Pawnee 135.62

Name & Address 3545 NW 58th Street

Well Total Depth 4173 feet

Oklahoma City, OK 73112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 390

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:00 am Day: 4 Month: February Year: 1986

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4173' PBTD 3795' Perfs at 3577-3761'; 2970-2558'

1st plug sand back to 3520' and push plug to 2500', sand back to 2450' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 140 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:15 pm Day: 4 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3520' and pushed plug to 2500' then sanded back to 2450' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 1 sack hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 140 sx cement.

Maximum pressure 150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2000' 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 11 1986

INV. NO. 12531

2-4

RECEIVED STATE CORPORATION COMMISSION

FEB 10 1986

CONSERVATION DIVISION Wichita Kansas

Signed J. H. Metzler (TECHNICIAN)