

15-145-01390-0000

1 070133

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 2-12-53

SW NW NW, SEC. 32, T 23 S, R 15 ^{XX} _{W/E}

4290 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Benson Unit Well # 207

Operator: Cities Service Oil & Gas Corp.
Name & Address 3545 W. 58th Street
Oklahoma City, OK 73112

County Pawnee 125.61

Well Total Depth 3865 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 386

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 3 Month: February Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3865' PBTD 3848' Perfs at 3594-3839'

1st plug sand back to 3540' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 140 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2:00 pm Day: 3 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3540' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, released 8 5/8" wiper plug and pumped 140 sx cement.

Maximum pressure 250 psi and shut in 50 psi

Remarks: Recovered 2700' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED (add remarks) observe this plugging.

RECEIVED signed Dan Goodrow
STATE CORPORATION COMMISSION (TECHNICIAN)

DATE FEB 11 1986

FEB 10 1986

INV. NO. 12530

CONSERVATION DIVISION

FORM CP-2/3 Rev. 01-84