

15-145-01388-0000

1 010077

API NUMBER 15- Completed 8-11-52

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW NW, SEC. 32, T 23 S, R 15 W/E

3630 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Benson Unit Well # 205

Operator: Cities Service Oil & Gas Corp.  
Name & Address 3545 NW 58th Street  
Oklahoma City, OK 73112

County Pawnee 127.50

Well Total Depth 3923 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 392

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 pm Day: 21 Month: January Year: 19 86

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3923' PBTD 3680' Perfs at 3549-3647'

1st plug sand back to 3520' and dump 5 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

released 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 12:45 pm Day: 21 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3520' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel

1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

1-27-86 JAN 27 1986

Maximum pressure 400 psi and shut in 100 psi

CONSERVATION DIVISION

Remarks: Recovered 2500' 5 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

INVOICED

(if desired) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE FEB 5 1986

INV. NO. 12335 1-21