

1090392

145-60002-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Completed 3-10-52
SW NE NW, SEC. 32, T23 S, R 15 W/E

4290 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: Cities Service Oil & Gas Corp.
Name & Address: 3545 NW 58th Street
Oklahoma City, OK 73112

Lease Name Benson Unit Well # 202
County Pawnee 127.99
Well Total Depth 3938 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 411

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:30 am Day: 9 Month: January Year: 19 86

Plugging proposal received from Neil Peddicord
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3937' PBD 3918' Perfs at 3552-3783'
1st plug sand back to 3500' and dump 5 sx cement on top of sand through bailer
2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 am Day: 9 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 3500' and dumped 5 sx cement on top of
sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement,
10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JAN 16 1986

Maximum pressure 300 psi and shut in 100 psi

CONSERVATION DIVISION
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 600' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-16-86
INV. NO. 12087
1-9

Signed Robert Barburton
(TECHNICIAN)