

10-23

To: <sup>1</sup> 040479  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 13-145-21,317-0000  
C SE SE, SEC. 34, T 23 S, R 15 W/EX

TECHNICIAN'S PLUGGING REPORT

660 feet from S section line  
660 feet from E section line

Operator License # 5086

Lease Name Evans Well # 1

Operator: Pintail Petroleum Ltd.  
Name & Address 412 E. Douglas, Suite One  
Wichita, KS 67202

County Pawnee 133.73

Well Total Depth 4115 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rockhold Engineering, Inc. License Number 5111

Address Box 698, Great Bend, KS 67530

Company to plug at: Hour: 3 p.m. Day: 23 Month: 10 Year: 19 90

Plugging proposal received from Dbacon Pulley

(company name) Rockhold Engineering, Inc. (phone) 316-792-2506

were: 4 1/2" at 4112' w/150 sx cement. Perfs at 4042-98'  
1st plug sand back to 3990' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 150 sx cement.

Plugging Proposal Received by Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3:30 p.m. Day: 23 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 3990' and dumped 4 sx cement on top of sand  
bridge through bailer.

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 500 psi and shut in 350 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2595' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 11-6-90  
INV. NO. 29845

STATE CORPORATION COMMISSION  
OCT 30 1990  
10-30-90  
CONSERVATION DIVISION  
Wichita, Kansas

Signed [Signature]  
(TECHNICIAN)