

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-30004-00-02

Spot: NESWSWSE

Sec/Twnshp/Rge: 23-23S-15W

430 feet from S Section Line, 2310 feet from E Section Line

Lease/Unit Name: GRIZZELL OWWO

Well Number: 2-A

County: PAWNEE

Total Vertical Depth: 4150 feet

Operator License No.: 3180

Conductor Pipe: Size

feet:

Op Name: DEUTSCH, KENT A. DBA DEUTSCH OIL

Surface Casing: Size 8.625

feet: 221

8134.88
WITH 175 SX CMT

Address: 8100 E. 22ND ST. N.

Production: Size 5.5

feet: 4150

WITH 100 SX CMT

WICHITA, KS 67226

Liner: Size

feet:

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 05/08/2002 10:30 AM

Plug Co. License No.: 6901

Plug Co. Name: D S & W WELL SERVICING, INC.

Proposal Revd. from: VERNON PHLUGHOEFT

Company: D S & W

Phone: (620) 587-3361

Proposed Plugging Method: BOTTOM PLUG SAND TO 2039' & 5 SX CMT. 1ST PLUG AT 1000' WITH 50 SX CMT & 10 SX GEL. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 05/08/2002 11:45 AM

KCC Agent: RICHARD LACEY

Actual Plugging Report:

PBTD 2121'. PERFS AT 2089-97'. SAND TO 2039' & 5 SX CMT WITH DUMP BAILER. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 840' WITH 10 SX GEL - 50 SX CMT. 2ND PLUG AT 250' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED

MAY 13 2002

KCC WICHITA

6-13-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 860' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

INVOICED

MAY 10 2002

DATE

5-14-02

TRV. NO.

2002061774

FORM SP-2/3

80

AKA
Grizzell 1-23