

1041317

TO: STATE CORPORATION COMMISSION

API NUMBER 15-145-21,304-0000
SE NE NE SEC. 24, T 23 S, R 15 W

9-30

CONSERVATION DIVISION - PLUGGING SECTION 4290 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME JOHNSON WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY PAWNEE 133.90

OPERATOR LICENSE # 7383

WELL TOTAL DEPTH 4120 FEET

OPERATOR: GRADY BOLDING CORPORATION PRODUCTION CSG: SIZE 5 1/2" FEET 4119

NAME AND PO BOX 486 SURFACE CASING: SIZE 8 5/8" FEET 446'

ADDRESS ELLINWOOD, KS 67526-0486

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 30 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM MIKE KELSO

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 3774-76, 3780-85, 3805-08

1ST PLUG SANDED BACK TO 3725' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

LOADED HOLE WITH GEL & SPOT PLUGS THRU 5 1/2" CASING.

2ND PLUG AT 1050' WITH 50 SX CEMENT. 3RD PLUG AT 460' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 30 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT 10-14-98

1ST PLUG SANDED BACK TO 3725' AND PUT 5 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

LOAD HOLE WITH GEL AND SPOT PLUGS THRU 5 1/2" CASING.

2ND PLUG AT 1050' WITH 50 SX CEMENT. 3RD PLUG AT 460' WITH 50 SX CEMENT.

4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1610' OF 5 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

10-15-98
60115
c

10-14-98
STATE CORPORATION COMMISSION
RECEIVED