

9-11

To: 1 051204
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-20,356-0000
SW SW, SEC. 28, T 23 S, R 15 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5708

660 feet from S section line

4620 feet from E section line

Operator: Aspen Drilling Company
Name & Address Box 783
Great Bend, KS 67530

Lease Name City of Macksville Well # 1

County Pawnee 68.84

Well Total Depth 2118 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Aspen Drilling Company License Number 5708

Address Box 783, Great Bend, KS 67530

Company to plug at: Hour: 10 a.m. Day: 11 Month: 9 Year: 19 89

Plugging proposal received from Robert Pelster

(company name) Aspen Drilling Company (phone) 316-792-2469

were: 4 1/2" at 2117' PBTD 2093' Perfs at 2010-20, 2026-36'

1st plug bottom through 2" tubing with 25 sx cement,

2nd plug pump 20 sx cement at 950',

3rd plug pump 30 sx cement at 450', 4th plug pump 5 sx cement at 40',

5th plug pump 125 sx cement down 8 5/8" & 4 1/2" annulus.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 2:25 p.m. Day: 11 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT Spotted all plugs through tubing,

1st plug at 2020' with 10 sx gel and 25 sx cement,

2nd plug at 950' with 20 sx cement,

3rd plug at 450' with 30 sx cement,

4th plug at 40' with 5 sx cement,

5th plug pumped down 8 5/8" X 4 1/2" annulus with 125 sx cement. Maximum pressure 300 psi and

shut in 100 psi. Used common cement by Allied. No casing recovery.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION

SEP 13 1989
9-13-89
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 9-22-89

Signed Richard W. Lucey
(TECHNICIAN)

RWL

INV. NO. 25932