

To: 1 052134
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

5-14 API NUMBER 15- 145-20,236-0000
NW SE SW, SEC. 30, T 23 S, R 15 W/X

TECHNICIAN'S PLUGGING REPORT

Operator License / 3911
Operator: RAMA OPERATING CO. INC.
Name & Address P.O. Box 159
Stafford, KS 67578-0159

990 feet from S section line
3630 feet from E section line
Lease Name Garvin "A" Well # 1
County Pawnee 99.94
Well Total Depth 3075 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing License Number _____
Address _____

Company to plug at: Hour: 8 a.m. Day: 14 - Month: 5 Year: 19 97
Plugging proposal received from Robert Austin
(company name) RAMA Operating Co., Inc. (phone) 316-234-5191

work: 5 1/2" at 3069' w/180 sx cement, PBTD 3069', Perfs at 2015-19, 2594-99, 2881-82, 3008-15'
Anhydrite at 995'. Attempted to drill out collapsed pipe, reached 1400'. Attempted to pull
pipe at 1205'

1st plug pump 2 sx hulls and 35 sx cement down casing to perfs at 2015-19'. Perforate casing
at Anhydrite. 2nd plug circulate 335 sx cement down casing.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5:15 p.m. Day: 14 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug ran tubing to 907'. Could not get inside 5 1/2" stub. Spotted
50 sx cement (60/40 Pozmix 4% cc). Waited on cement 2 hrs. Tagged cement at 744'.

2nd plug ran tubing to 722' and spotted 250 sx 60/40 Pozmix 6% gel and 50 sx 60/40 Pozmix.
Good circulation. No cement to surface. Waited on cement 4 hrs. Tagged cement at 344'.

3rd plug ran tubing to 310' and circulated cement to surface with 85 sx 60/40 Pozmix 4% cc.

Remarks: Cemented by Allied. Recovered 886' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Richard W. Lacy
(TECHNICIAN)

DATE 5-23-97

INV. NO. 48169

5-14

5-21-97
RECEIVED
MAY 21 1997
PLUGGING SECTION