

1052381

15-145-00805-00-01

TO: STATE CORPORATION COMMISSION

API NUMBER DRILLED 01/04/1953
SW NE SW SEC. 30, T 23 S, R 15 W

CONSERVATION DIVISION - PLUGGING SECTION 1650 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME RILEY B WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY PAWNEE

OPERATOR LICENSE # 5363 WELL TOTAL DEPTH 4052 FEET

OPERATOR: BEREXCO, INC. PRODUCTION CSG: SIZE 5 1/2" @ 4078' WITH 150 SX

NAME AND PO BOX 723 SURFACE CASING: SIZE 8 5/8" @ 350' WITH 225 SX

ADDRESS HAYS, KS 67601

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 628, GREAT BEND, KS 67530-0628

COMPANY TO PLUG AT: HOUR: 11:30 AM DAY: 15 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MARK LEIKER

(COMPANY NAME) ALLIED CEMENTING (PHONE) 316-793-5861

WERE: PERFS AT 3260-3811

BOTTOM PLUG SET CIBP AT 3330 & 4 SX CEMENT. 1ST PLUG AT 1550' WITH 100 SX CEMENT AT PERFS

2ND PLUG AT 1000' CIRCULATE TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY STEVE DURRANT

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:05 PM DAY: 27 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT SET CIBP @ 3330' & 4 SX CEMENT WITH BAILER. PRESSURE TESTED CASING

TO 400 PSI. PERFED AT 1550' PUMPED 100 SX CEMENT DISPLACED TO 1400'. WENT ON VACUUM. TRIED

TO TAG CEMENT 1 HR. LATER. NONE FOUND. PUMPED 100 SX CEMENT DISPLACED TO 1000. 0 PSI SHUT IN.

SDON. ALLIED PUMPED 60/40 POZMIX 6% GEL. ON 3/16/00 TAGGED CEMENT AT 1397'. PERFED AT 1000'

AND PUMPED 150 SX CEMENT DISPLACED TO 600'. SHUT IN PRESSURE 350 PSI. PERFORATED AT 500'

PUMPED 200 SX STARTED CIRCULATION AT 100 SX CIRCULATED 10 BBL WATER TO PIT. 3/16/00 PUMPED

60/40 POZ 2% GEL 4% CC. 3/27/00 FOUND CEMENT TOP AT 178'. PUMPED 30 SX DOWN 5 1/2". PUMPED 30

SX DOWN 8 5/8" X 5 1/2" ANNULUS.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacy
(TECHNICIAN) FORM CP-2/3

