

To: 1 052136 S-22

API NUMBER 15- 185-23,041-0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

SW NW SE, SEC. 16, T 21 S, R 12 WXX

1650 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 6166

Lease Name Rose Well # 1

Operator: Bill Chew, Inc.

County Stafford 120.25

Name:

Address P.O. Box 90

Well Total Depth 3700 feet

Lyons, KS 67554-0090

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 299

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 22 - Month: 5 Year: 1997

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 5 1/2" at 3695' w/125 sx cement, CIBP at 3500', Perfs at 3343-45, 3442-44'

1st plug sand back to 3290' and dump 5 sx cement on top of sand through bailer,

2nd plug at 700' with 50 sx cement,

3rd plug at 300' with 50 sx cement,

4th plug at 40-0' with 10 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:35 a.m. Day: 22 Month: 5 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3290' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 75 sx cement, 10 sx gel, 100 lbs. hulls, and 125 sx cement.

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.
(If additional description is necessary, use BACX of this form.)

Observe this plugging.

INVOICED
DATE JUN 05 1997
INV. NO. 48222

Signed Steve Durrant (TECHNICIAN)

6-2-97
RECEIVED
KANSAS CORP COM
JUN 11 1997