

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH-MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23129-00-00
Spot: E2NESW Sec/Twnshp/Rge: 11-21S-11W
1890 feet from S Section Line, 2310 feet from W Section Line
Lease/Unit Name: SCHAFFER A 11 Well Number: 8-11
County: STAFFORD Total Vertical Depth: 3500 feet

Operator License No.: 5056
Op Name: HOLL, F.G., COMPANY L.L.C.
Address: 9431 E CENTRAL, SUITE 100
WICHITA, KS 67206

Conductor Pipe: Size feet: 8/13.75
Surface Casing: Size 8.625 feet: 226 WITH 250 SX CMT
Production: Size 4.5 feet: 3492 WITH 225 SX CMT
Liner: Size feet:

Well Type: OG UIC Docket No: Date/Time to Plug: 01/28/2003 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: SAND BACK TO 3311' WITH 4 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 250' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT. 10 SX GEL FOR GEL SPACER.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 01/28/2003 4:45 PM KCC Agent: SCOTT ALBERG


Actual Plugging Report:

PBTD 3412'. PERFS AT 3387-3391'. SAND BACK TO 3311' WITH 4 SX CMT. 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 480'. 2ND PLUG SPOT 50 SX CMT AT 230'. 3RD PLUG SPOT 10 SX CMT AT 0-40'.

Remarks: USED 60/40 POZMXI 6% GLE BY ACID SERVICES. RECOVERED 1800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



RECEIVED (TECHNICIAN)
FEB 06 2003
KCC WICHITA
2-6-03
INVOICE
DATE 2-10-03
NO. 2003061172