

1 080187

15.185.01385.0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Comp. 1-19-64
NW SE NW, SEC. 11, T 21 S, R 11 W ~~EX~~
3630 feet from ~~W~~ SE Corner of
3630 feet from ~~W~~ SE Corner of

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Schafer Well # 1

Operator: F. G. Holl

County Stafford

Name & Address 6427 East Kellogg

Well Total Depth 3426 111.35 feet

Wichita, KS 67207

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 266

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 8 Month: August Year: 1984

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 3418' PBTB 3386' Perfs 3358-64

1st plug sand back to 3300' and dump 4 sx cement on top of sand through bailer

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125 sx

cement

Plugging Proposal Received by J. M. [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 pm Day: 8 Month: August Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3418' PBTB 3386' Perfs 3358-64'

1st plug sanded back to 3300' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 125

sx cement.

Maximum pressure 600 psi and shut in pressure 300 psi

Remarks: They recovered 2700' of 4 1/2" casing. Cemented by Allied.
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 8-17-84

INV. NO. 3199

RECEIVED
STATE CORPORATION COMMISSION
Signed

8-16-84 AUG 16 1984

J. M. [Signature]
(TECHNICIAN)

CONSERVATION DIVISION
Wichita, Kansas