

6-24

To: 1 031084
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-22,687-0000

W/2 NW NW, SEC. 11, T 21 S, R 11 W/E

4860 4620 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5056

Lease Name Schafer Well # 7-11

Operator: F.G. Holl Company

County Stafford 109.69

Name & Address P.O. Box 780167

Well Total Depth 3375 feet

Wichita, KS 67278-0167

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 277

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 129, Sterling, KS 67579

Company to plug at: Hour: 2 a.m. Day: 24 Month: 6 Year: 19 90

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-278-2131

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 482-90'

1st plug at 550' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 15 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4:15 a.m. Day: 24 Month: 6 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 550' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 60' with 15 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1990

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.
(If additional description is necessary, use BACK of this form.)

INVOICED (I do not) observe this plugging.

Signed Steve J. Dumont (TECHNICIAN)

DATE 7-2-90

INV. NO. 28509

FORM MUST BE TYPED
FORM C-1 12/88

State of Kansas
NOTICE OF INTENTION TO DRILL 185-22,687

FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date June 16, 1990
month day year

C.W2 NW NW Sec 11 Twp 21 S, Rg 11W West

OPERATOR: License # 5056
Name: E. G. HOLL COMPANY
Address: P.O. BOX 780167
City/State/Zip: Wichita, Kansas 67278-0167
Contact Person: Elwyn H. Nagel
Phone: (316) 684-8481

4620 feet from South line of Section
4950 feet from East line of Section
(Note: Locate well on Section Plat Below)

CONTRACTOR: License #: 5142
Name: Sterling Drilling Company

County: Stafford
Lease Name: SCHAFER Well #: 7-11
Field Name: Spider

Well Drilled For: Well Class: Type Equipment:
X Oil Inj X Infield X Mud Rotary
Gas Storage Pool Ext. Air Rotary
OWO Disposal Wildcat Cable
Seismic: # of Holes

Is this a Prorated Field? yes X no
Target Formation(s): LKC, CONG, SIMP, ARB.
Nearest lease or unit boundary: 330'
Ground Surface Elevation: 1765 (Estm) feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Depth to bottom of fresh water: 140'
Depth to bottom of usable water: 220'
Surface Pipe by Alternate: X, 1 2
Length of Surface Pipe Planned to be set: 240'
Length of Conductor pipe required: N/A
Projected Total Depth: 3480'
Formation at Total Depth: Arbuckle
Water Source for Drilling Operations: X well farm pond other

If OWO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

240' Alt. T. Reg.
DWR Permit #: (Applied for by Sterling Drig.)
Will Cores Be Taken?: yes X no
If yes, proposed zone:

Directional, Deviated or Horizontal wellbore? yes X no
If yes, total depth location:

Exp. 6/15/90

AFFIDAVIT

240' Alt. T. Reg.
RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1990

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.
It is agreed that the following minimum requirements will be met:

Pusher Vaughn Thompson
SPUD DATE 6-18-90 INIT. R.L.L.
LENGTH SURFACE PLANNED 240
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done X bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 277 CONDUCTOR
ANHYDRITE T-482 B-490 ELEVATION
TD 3375 FORMATION Arb. 3334
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ 5 Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ 550 Ft. W/ 50 SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ 300 Ft. W/ 50 SX
40' Plug @ 60 Ft. W/ 15 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well) Pond
Hauling
TECHNICIAN None DATE
TYPE OF CEMENT 60/40 60/10
STARTING TIME 2:00 (AM/PM) DATE 6-24-90
COMPLETION TIME 4:15 (AM/PM) DATE 6-24-90
CEMENT COMPANY B.V. T. Co. R. Locay