

1050147

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NOT AVAILABLE
NW SE, SEC. 12, T 21 S, R 23 W/E
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5229

Lease Name Hays "AB" Well # 1

Operator: Phillips Petroleum Company

County Hodgeman

Name & Address Box 287,

Well Total Depth 4467 145.17 feet

Great Bend, KS 67530

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 404

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pullers License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 am Day: 14 Month: February Year: 19 84

Plugging proposal received from Gene Smith

(company name) Kelso Casing Pullers (phone) 316-938-8186

were: 5 1/2 set at 4448 Top Perfs 4336 - 44 PBT 4446

1st plug sand back to 4290' and dump 5 sx cement on top of sand

2nd plug squeeze head with 3 hulls, 25 sx cement and released 8 5/8" rubber plug and dumped an additional 200 sx cement.

Maximum pressure 1000# and shut-in pressure 400#

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:45 am Day: 14 Month: February Year: 19 84

ACTUAL PLUGGING REPORT 5 1/2 set at 4448 Top Perfs 4336 - 44 PBT 4446

1st plug sand back to 4290' and dump 5 sx cement on top of sand

2nd plug squeeze head with 3 sx hulls, 25 sx cement and released 8 5/8" rubber plug and dumped an additional 200 sx cement.

Maximum pressure 1000# and shut-in pressure 400#

RECEIVED
STATE CORPORATION COMMISSION

FEB 22 1984 2-22-84

Remarks: They recovered 2190' 5 1/2 Use 60/40 Pozmix 2% gel 3% cc by Sun Cementing
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 2-23-84 (did not observe this plugging.)

INV. NO. 0301

Signed Richard W. Lacey
(TECHNICIAN)