

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-30360-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 3-21S-12W
330 feet from S Section Line, 2310 feet from E Section Line
Lease/Unit Name: WOLF Well Number: 2
County: STAFFORD Total Vertical Depth: 3581 feet

Operator License No.: 31199
Operator Name: D J OIL OPERATIONS
Address: 305 E. 6TH
ELLINWOOD, KS 67526

Conductor Pipe: Size feet:
Surface Casing: Size 10.75 feet: 258 WITH 300 SX CMT
Production: Size 5.5 feet: 3495 WITH 125 SX CMT
Liner: Size feet: \$116,38

Well Type: SWD UIC Docket No: D14601.0 Date/Time to Plug: 11/01/2000 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed
Plugging
Method:

ACCORDING TO THE RULES AND REGULATIONS OF THE STATE OF KANSAS.

Plugging Proposal Received By: STEVE DURRANT
Date/Time Plugging Completed: 11/01/2000 1:20 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)
KCC Agent: RICHARD LACEY

Actual Plugging Report:

OPEN HOLE AT 3495-3581'. 642' ANHYDRITE. TOC = 2683'. PULLED 1250' OF ROTTEN 2 3/8" TUBING. TRIED TO RUN OVERSHOT INTO FISH. HUNG UP AT 250'. WORKED 2 7/8" TUBING TO 1510'. PUMPED 10 SX GEL WITH 500# HULLS MIXED IN FOLLOWED WITH 100 SX 60/40 POZMIX 6% GEL 3% CC. GOOD CIRCULATION UP 5 1/2' & 10 3/4'. PULLED TUBING TO 660'. PUMPED 275 SX OF 60/40 POZMIX 6% GEL, CIRCULATING CEMENT TO SURFACE UP BOTH 5 1/2" AND 5 1/2" X 10 3/4" ANNULUS. PULLED TUBING, TOPPED OFF HOLE WITH 20 SX CMT. STAYED FULL.

RECEIVED
STATE CORPORATION COMMISSION
11-13-00
NOV 15 2000

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

CONSERVATION DIVISION
Wichita, Kansas

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

INVOICED
DATE 11/14/00
INV. NO. 2001060974

NOV 08 2000

Form CP-2/3

MD