

1 060594

15-185-30270-0001

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Comp 7-20-66

SW NW SW, SEC. 22, T 21 S, R 11 W/E

1650 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046

Lease Name Rugan Well # 1 SWD

Operator: Raymond Oil Company

County Stafford 119.64

Name & Address One Main Place, Suite 900

Well Total Depth 3681 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 206

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 18 Month: June Year: 19 85

Plugging proposal received from Neil Peddicord

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 3610', PBD 3610' Open Hole 3610-3681

1st plug sand back to 3510' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 20 sx gel, 80 sx cement, 15 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi

(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 3:30 pm Day: 18 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3510' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 20 sx gel, 80 sx cement, 15 sx gel, 1 sack hulls and 150 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

6-21-85 JUN 21 1985

Maximum pressure 600 psi and shut in 200 psi

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied- Recovered 1700' 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 6-29-85

INV. NO. 8683

Signed Paul A. Luthi
(TECHNICIAN)