

1 120317

10-6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-185-21,131-0000
200' W of
SE SE SE, SEC. 20, T 21 S, R 14 W/E

330 feet from S section line
530 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5427

Lease Name Fullerton Well # 1

Operator: D.R. Lauck Oil Company, Inc.

County Stafford 123.33

Name & Address 221 South Broadway, Suite 400

Well Total Depth 3795 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 255

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:30 a.m. Day: 6 Month: 10 Year: 19 89

Plugging proposal received from Mike Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 3795' PRTD 3785' Perfs at 3754-62' Elevation 1946' KB 10-12-89

1st plug sand 4 1/2" casing back to 3700' and dump 4 sx cement on top of sand through bailer.

2nd plug pump 50 sx cement at 900' through 4 1/2" casing,

3rd plug pull all casing and pump 400 lbs. hulls and 150 sx cement with hulls mixed in cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12 p.m. Day: 6 Month: 10 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 3700' and dumped 4 sx cement on top of sand through bailer,

2nd plug shot 4 1/2" casing at 2600' and layed down 1700', and pumped 50 sx cement at 900',

3rd plug layed down all 4 1/2" casing and pumped through 8 5/8" casing with 400 lbs. hulls, and 150 sx cement with 300 lbs. hulls mixed in cement.

No pumping pressure, slight vacuum on shut in. Ran line and checked plug set at 900', line stacked at 750'.

Remarks: Used 60/40 Pozmix 6% gel 2% cc by Allied. Recovered 2600' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-13-89

Signed Duane Rankin
(TECHNICIAN)

INV. NO. 26140