

1 080298

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NW NE NW
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 185-21,074-0000 *R*

4950 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5357

Lease Name Strobel Well # 1

Operator: Frank J. Black

County Stafford 123.50

Name & Address P. O. Box 250

Well Total Depth 3800 feet

McPherson, KS 67460.

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address P. O. Box 206, Geneseo, KS 67444

Company to plug at: Hour: 1:00 pm Day: 3 Month: January Year: 19 85

Plugging proposal received from Allen Nicholas

(company name) Nicholas Casing Pulling (phone) 316-884-6467

were: 5 1/2" set at 3799' Perfs at 3564'

1st plug sand back to 3510' and dump 5 sx cement on top of sand

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:34 pm Day: 3 Month: January Year: 19 85

ACTUAL PLUGGING REPORT 5 1/2" set at 3799' Perfs at 3564'

1st plug sanded back to 3510' and dumped 5 sx cement on top of sand, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 100 sx cement.

STATE CORPORATION COMMISSION

Maximum pressure 500 psi and shut in 300 psi

07 1985 1-7-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2300' 5 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Halliburton additional description is necessary, use BACK of this form.)

INVOICED

I (did / did not) observe this plugging.

DATE 1-13-85

Signed J. H. Metz (TECHNICIAN)

INV. NO. 6448