

15.185.30372.0000

State of Kansas



WM. H. AVERY	Governor
WILLIAM L. MITCHELL	Chairman
JAMES O. GREENLEAF	Commissioner
HARRY G. WILES	Commissioner
RAYMOND B. HARVEY	Secretary
E. EDWARD JOHNSON	Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
FEB 6 1967
2-6-67
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed January 26, 1967

Dear Sir:

Mr. Jim Davenport of Sage Drilling, Co., Inc. has this date requested permission to plug the following described well:

Mr. Davenport guarantees payment of the plugging fee.

Operator's full Name: Circle Oil Company, Inc.

Complete Address: 500 Bitting Bldg., Wichita, Kansas

Lease Name: Bordewick Well No. # 1

Location: SE NW NE Sec. 24 Twp. 21 Rge. 14 (E)(W) W

County Stafford Total Depth 3732' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Davenport was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated. Fill hole with drilling mud to 225', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent